# SAMPLING ROUND SCHEDULE

Fungal and microbial colonisation of tropical educational building exteriors: molecular characterisation and campus air-quality context at UTS Sibu
Dr Armstrong Ighodalo Omoregie | BERI, School of Built Environment, UTS | UTS Matching Grant, Cycle 1/2027

| Round | Month | Seasonal phase | Note |
|---|---|---|---|
| **R1** | June 2027 | Southwest monsoon | |
| **R2** | September 2027 | Southwest monsoon, late phase | |
| **R3** | December 2027 | Northeast monsoon | |
| **R4** | March 2028 | Northeast monsoon, late phase | |
| **R5** | June 2028 | Southwest monsoon | *twelve-month repeat of R1* |
| **R6** | September 2028 | Southwest monsoon, late phase | *twelve-month repeat of R2* |

Rounds 1 to 4 constitute a complete annual seasonal round covering both monsoon phases. Rounds 5 and 6 resample the Round 1 and Round 2 phases exactly twelve months later, giving paired year-on-year observations for two of those phases.

Up to two additional rounds are triggered opportunistically during regional haze episodes.

At each round, 36 fixed points are sampled: 4 buildings x 4 orientations x paired colonised and clean surfaces, giving 32 wall points, plus 4 roof points. Three replicate swabs per point are composited, giving 36 samples per round and 216 composited samples across the six rounds.

The first round falls three months after commencement so that the SBC permit can be applied for and issued first. Sampling closes in September 2028 so that the remaining molecular work, analysis, both manuscripts and grant closure complete within the term ending 28 February 2029.